

## UPACMIC (LIFE12 ENV/FI/000592)

# UTILISATION OF BY-PRODUCTS AND ALTERNATIVE CONSTRUCTION MATERIALS IN NEW MINE CONSTRUCTION











## UPACMIC (LIFE12 ENV/FI/000592)

Utilisation of by-products and alternative construction materials in new mine construction




- Started in July 2012 and the project will end in August 2020
- Co-ordinated by Ramboll Finland, other partners are Fortum Environmental Construction and Suomen Maastorakentajat
- Area: secondary materials in mining sector
- Funded by the EU LIFE financial instrument, Ministry of the Environment of Finland and Yara Finland
- Implementation
  - Development of material mixtures suitable for the pilot applications:
    cover structure, bottom structure and reactive wall/barrier



- Monitoring of the impact of the project actions
  - Studying the project impact on the main target audience and on the environmental problem targeted
- Communication and dissemination actions
- Management actions




#### **UPACMIC LOCATIONS**





#### **LABORATORY TESTS**





Column tests according to the standard CEN/TS 14405

Column ID	Materials
HK1	Gold enrichment sand
HK2	Nickel enrichment sand
HK3	Gold enrichment sand, nickel enrichment sand
HK4	Moraine, gold enrichment sand, nickel enrichment sand
HK5	Gold enrichment sand + 15 % biotite, nickel enrichment sand
HK6	Stabilised gold enrichment sand + piled fly ash, nickel enrichment sand
HK7	Stabilised gold enrichment sand + fly ash, nickel enrichment sand
HK8	Stabilised nickel enrichment sand + fly ash, nickel enrichment sand
HK9	Lime stabilised gold enrichment sand
HK10	Stabilised gold enrichment sand + lime, gold enrichment sand, nickel enrichment sand



#### **PILOTING CONSTRUCTION IN HITURA MINE, 2018**





Levelled enrichment sand waiting to be covered



Fibre clay (OPA) from Oulu



UPACMIC 6.6.2018

Covered fibre clay

#### **UPACMIC**



Structures made of alternative materials can impact on the quality and amount of the seeping water (-> pH, solubility of metallic elements, water permeability)



Studies are yet unfinished and will further continue



Piloting site possibilities are yet searched – do you know a site where bottom structures or reactive barriers could be needed?



http://projektit.ramboll.fi/life/upacmic/index\_eng.htm

Twitter @UPACMIC

### **THANK YOU!**

pentti.lahtinen@ramboll.fi, +358 400 939 082 harri.jyrava@ramboll.fi, +358 400 732 593 tarja.niemelin@ramboll.fi, +358 40 6877 809









